

KCC OIL/GAS REGULATORY OFFICES

Date: 08/14/12

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 8996
 Op Name: Mid-Continent Resources, Inc.
 Address 1: P.O. Box 399
 Address 2:
 City: Garden City
 State: KS Zip Code: 67846 -
 Operator Phone #: (620) 275-2963

API Well Number: 15-135-25401-00-00
 Spot: NE-SE-NW-SE Sec 23 Twp 19 S Rng 22 E / W
 1700 Feet from N / S Line of Section
 1550 Feet from E / W Line of Section
 GPS: Lat: 38.38293 Long: 99.71986 Date: 8/14/12
 Lease Name: Gillig Well #: 6-23
 County: Ness

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Scott Corsair.

Findings:

1:35 p.m.
8 5/8" was set @ 224' with 150 sx cement. 5 1/2" was set @ 4399' with 179 sx cement on the primary cementing job. Company opened the port collar @ 1480'. Swift Services, Inc. pumped 150 sx SMD cement, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.

SMD cement with 1/4# floseal by Swift Services, Inc.

GPS converted footages are 1697' FSL & 1543' FEL.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren
Eric MacLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
AUG 23 2012
KCC DODGE CITY

RECEIVED
AUG 27 2012
KCC WICHITA

Form: _____

AM7