

KCC OIL/GAS REGULATORY OFFICES

Date: 08/20/12

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767
 Op Name: Ritchie Exploration, Inc.
 Address 1: P.O. Box 783188
 Address 2: _____
 City: Wichita
 State: KS Zip Code: 67278 -3188
 Operator Phone #: (316) 691-9500

API Well Number: 15-057-20830-00-00
 Spot: NE-SE-SW Sec 17 Twp 28 S Rng 28 E / W
1620 Feet from N / S Line of Section
2310 Feet from E / W Line of Section
 GPS: Lat: _____ Long: _____ Date: 8/20/12
 Lease Name: Sanko Well #: 2
 County: Ford

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Gary Rowe.

Findings:

4:05 p.m.
 8 5/8" was set @ 358'. 5 1/2" was set @ 5266' with 175 sx cement on the primary cementing job.
 Company opened the port collar @ 1487'. Basic Energy Services pumped 275 sx cement with 175# hulls, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.

60/40 poz, 6% gel by Basic Energy Services.

GPS converted footages are 1615' FNL & 2303' FWL.

Verification Sources:

Photos Taken: 0

- | | | |
|---|---|-------------------------------------|
| <input type="checkbox"/> RBDMS | <input type="checkbox"/> KGS | <input type="checkbox"/> TA Program |
| <input type="checkbox"/> T-1 Database | <input type="checkbox"/> District Files | <input type="checkbox"/> Courthouse |
| <input checked="" type="checkbox"/> Other: <u>On-site witness</u> | | |

By: Eric Maclaren
Eric Maclaren

Retain 1 Copy District Office
 Send 1 Copy to Conservation Division

RECEIVED

AUG 23 2012

KCC DODGE CITY

RECEIVED

AUG 27 2012

KCC WICHITA

Form: _____