

KCC OIL/GAS REGULATORY OFFICES

Date: 08/14/12

District: 1

Case #: _____

☐ New Situation

☐ Lease Inspection

☒ Response to Request

☐ Complaint

☐ Follow-Up

☒ Field Report

Operator License No: 8914

API Well Number: 15-135-25439-00-00

Op Name: H & C Oil Operating, Inc.

Spot: SW-SE-NW-SW Sec 19 Twp 17 S Rng 26 ☐ E / ☒ W

Address 1: P.O. Box 86

1550 Feet from ☐ N / ☒ S Line of Section

Address 2: _____

800 Feet from ☐ E / ☒ W Line of Section

City: Plainville

GPS: Lat: 38.55656 Long: 100.24490 Date: 8/14/12

State: KS Zip Code: 67663 -0086

Lease Name: Dinges Well #: 19-1

Operator Phone #: (785) 434-7434

County: Ness

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

None.

Findings:

1:35 p.m.

8 5/8" was set @ 211' with 160 sx cement. 5 1/2" was set @ 4538' with 200 sx cement on the primary cementing job. Company opened the port collar @ 2448'. Quality Oilwell Cementing pumped 250 sx cement, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required ☐ Yes ☒ No ☐

Date: _____

None. Alternate II cementing requirements have been met.

Multi-density cement with 1/4# floseal by Quality Oilwell Cementing.

GPS converted footages are 1551' FSL & 792' FWL.

Verification Sources:

Photos Taken: 0

<input type="checkbox"/> RBDMS	<input type="checkbox"/> KGS	<input type="checkbox"/> TA Program
<input type="checkbox"/> T-I Database	<input type="checkbox"/> District Files	<input type="checkbox"/> Courthouse
<input checked="" type="checkbox"/> Other: <u>On-site witness.</u>		

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

AUG 22 2012

KCC DODGE CITY

By: Eric MacLaren
Eric MacLaren

RECEIVED
AUG 27 2012
KCC WICHITA

Form: _____

8004