

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20380-00-00  
Spot: SWSWSWNE Sec/Twnshp/Rge: 27-28S-30W  
2490 feet from N Section Line, 2490 feet from E Section Line  
Lease Name: FREDRICK GOOSSEN Well #: 1-27(NE)  
County: GRAY Total Vertical Depth: 4275 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 2600       |             | WITH 2 SX CMT   |
| CIBP   |       | 2680       |             |                 |
| PROD   | 5.5   | 2928       | 2462        | WITH 100 SX CMT |
| SURF   | 8.625 | 1900       |             | WITH 825 SX CMT |

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/12/2012 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Revd. from: CHUCK TONER Company: FALCON EXPLORATION Phone: (620) 546-4752

Proposed Plugging Method: CIBP @ 2600' & 2 SX CMT. PLUG AT 1930' WITH 25 SX GEL & 50 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 09/12/2012 8:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 2600' WITH 2 SX CMT. 1ST PLUG AT 1922' WITH 25 SX GEL & 50 SX CMT.  
2ND PLUG AT 926' WITH 50 SX CMT. 3RD PLUG AT 511' WITH 40 SX CMT. 4TH  
PLUG AT 40' WITH 20 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2720 | 2730 |      |          |
| 2692 | 2706 |      |          |
| 2674 | 2680 |      |          |
| 2660 | 2660 |      |          |
| 2650 | 2656 |      |          |

RECEIVED  
SEP 21 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

SEP 13 2012

KCC DODGE CITY

Signed

Steve Pfeifer  
10/08/12 (TECHNICIAN)

AAW