

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21843-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 5-24S-21W
335 feet from S Section Line, 1353 feet from E Section Line
Lease Name: HELFRICH Well #: 2-5
County: HODGEMAN Total Vertical Depth: 4675 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	264		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/19/2012 11:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: EMIDIGO ROJAS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE
Date/Time Plugging Completed: 09/19/2012 1:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

RECEIVED
SEP 27 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GELI/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Daniel Bernasconi
09/19/12 (TECHNICIAN)

RECEIVED

SEP 20 2012

KCC DOUGGE CITY

1007