

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20621-00-00
Spot: SENE SW Sec/Twnshp/Rge: 4-17S-27W
1638 feet from S Section Line, 2972 feet from E Section Line
Lease Name: KUEHN Well #: 6
County: LANE Total Vertical Depth: 4529 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3850		WITH 4 SX CMT
PROD	4.5	4250	0	WITH 225 SX CMT
SURF	8.625	321		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2012 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: RUN BOND LOG & FIND CMT. PERFORATE ABOVE CMT. RUN TBG TO & CIRCULATE CASING. TIE ONTO CASING & PUMP 80 SX CMT OVER CASING VOLUME, THEN 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2012 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****HAD HOLES SQUEEZED @ 2810'-2892' W/10 SX CMT, 1470'-1630' W/185 SX CMT. HAD CMT IN HOLE AT 2725' FROM LAST SQUEEZE JOB.** CIBP @ 3850' WITH 4 SX CMT. RAN BOND LOG FOUND CMT @ 690'. PERFORATED @ 630'. RUN TBG TO 1500' & PUMPED 100 SX CMT. CMT CIRCULATED. PULLED TBG & PUMPED 125 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.**

Perfs:

Top	Bot	Thru	Comments
3910	4218		

RECEIVED
SEP 27 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Michael Maier
10/10/12 (TECHNICIAN)

RECEIVED

SEP 11 2012

KCC DODGE CITY

APU