

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21490-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 26-17S-11W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: BLOOMER Well #: 1
County: BARTON Total Vertical Depth: 3355 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3354	1550	
SURF	8.625	260		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMANN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped off w/ 5 sx cement.
Cut casing @ 1550'. Pulled to 1250'. Pumped 125 sx cement w/200 # hulls. Had cement circulate early. Hole in casing up high. Pulled 2 joints and found hole in casing. Tied to casing. Pumped 100 sx cement w/100 # hulls.
Pulled casing to 850' and pumped 50 sx cement.
Pulled casing to 500' and pumped 40 sx cement w/100 # hulls.
Pulled casing to 250'. Circulated cement to surface w/40 sx cement.
Pulled casing. Hole stayed full.

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
10/08/12 (TECHNICIAN)

CM

SEP 19 2012

RECEIVED
SEP 28 2012
KCC WICHITA