

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24611-00-00  
Spot: N2NWSWNE Sec/Twnshp/Rge: 17-20S-11W  
3780 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: S AND K Well #: 3  
County: BARTON Total Vertical Depth: 3305 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3301		125 SX
SURF	8.625	341		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2012 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMANN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/11/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped w/5 sx cement.  
Cut casing @ 1600'. Pulled casing to 1250' and pumped 125 sx cement w/200 # hulls.  
Pulled casing to 850' and pumped 50 sx cement.  
Pulled casing to 500' and pumped 40 sx cement w/100 # hulls.  
Pulled casing to 250'. Circulated cement to surface w/80 sx cement.  
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3301	3305		

RECEIVED  
SEP 28 2012  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie  
✓ 10/08/12  
(TECHNICIAN)

CM

Form CP-2/3

SEP 19 2012