

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20015-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 13-19S-2W
430 feet from S Section Line, 4850 feet from E Section Line
Lease Name: LOVETT Well #: 5
County: MCPHERSON Total Vertical Depth: 2959 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2930		100 SX
SURF	8.625	165		140 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/21/2012 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: _____ Phone: (620) 628-4428

Proposed Plugging Method: TO PLUG ACCORDING TO THE RULES AND REGULATIONS OF THE KCC

Plugging Proposal Received By: HUNTER CLARK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2012 12:30 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SANDED OFF PERFS AT 2880' WITH A 5 SX CAP. RUN TUBING DOWN TO 600' SET A 30 SX PLUG OF 60/40 4%. PULLED UP TO 250' PUMPED 450 LBS OF HULLS. THEN CIRCULATED 200 SX OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2930	2959	OH	
646	655		
624	630		

Remarks: QWS TICKET #5492

Plugged through: TBG

District: 02

Signed [Signature] LOVETT
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 01 2012
CONSERVATION DIVISION
WICHITA, KS