

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20270-00-00
Spot: NWSE Sec/Twnshp/Rge: 14-34S-20W
1982 feet from S Section Line, 1999 feet from E Section Line
Lease Name: LEMON RANCH Well #: 1
County: COMANCHE Total Vertical Depth: 5675 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4700		WITH 2 SX CMT
CIBP		5521		
PROD	5.5	5635	2410	WITH 150 SX CMT
SURF	8.625	580	0	WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4700' WITH 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2012 11:00 AM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT ON TOP. 1ST PLUG AT 900' WITH 10 SX GEL & 80 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4754	4762		

RECEIVED
OCT 09 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Daniel Bernasconi
10/09/12
(TECHNICIAN)

RECEIVED

OCT - 9 2012

KCC DODGE CITY