

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25472-00-00

Spot: SWSESWNW

Sec/Twnshp/Rge: 31-20S-26W

2316 feet from N Section Line,

780 feet from W Section Line

Lease Name: IRSIK - NESS

Well #: 1-31

County: NESS

Total Vertical Depth: 4615 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String Size

SURF 8.625

Depth (ft)

224

Pulled (ft)

Comment

WITH 150 SX CMT

Well Type: DH

UIC Docket No:

Date/Time to Plug: 09/27/2012 8:45 AM

Plug Co. License No.: 5929

Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: KEN MCGUIRE

Company: DUKE DRILLING CO., INC.

Phone: (316) 267-1331

Proposed
Plugging
Method:

1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: NONE

Date/Time Plugging Completed: 09/27/2012 11:00 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

Richard M. Lacey
10/10/12

(TECHNICIAN)

RECEIVED

OCT 09 2012

KCC WICHITA

AME