

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00313-00-00
Spot: NESWSE Sec/Twnshp/Rge: 19-24S-13W
1001 feet from S Section Line, 1685 feet from E Section Line
Lease Name: DUDREY Well #: 1
County: STAFFORD Total Vertical Depth: 4229 feet

Operator License No.: 104
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4206	0	WITH 150 SX CMT
SURF	8.625	205		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2012 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8881

Proposed Plugging Method: RUN TBG TO 3750'. PUMP 10 SX GEL & 40 SX CMT. PERFORATE @ 800'. RUN TBG TO 800' CIRCULATING CMT UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2012 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

WORKED TBG TO 2910' WITH MUCH DIFFICULTY. PUMPED 10 SX GEL & 50 SX CMT. HAD CIRCULATION UP 5 1/2" & 8 5/8" X 5 1/2" INDICATING CASING LEAKS. PULLED TBG OUT OF HOLE. PERFORATED 5 1/2" @ 800'. RAN TBG TO 810'. PUMPED 290 SX CMT. CIRCULATED CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. PULLED TBG & TOPPED OFF HOLE WITH 60 SX CMT.

Perfs:

RECEIVED
OCT 11 2012
KCC WICHITA

Remarks: CONTROL NUMBER:20120042-003 USED 60/40 POZMIX 45 GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT - 8 2012
KCC WICHITA

R. Lacey