

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03302-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 19-11S-16W  
330 feet from S Section Line, 990 feet from W Section Line  
Lease Name: SLIMMER Well #: 4  
County: ELLIS Total Vertical Depth: 3337 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3328		0 SX
SURF	8.675	1006		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/12/2012 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY INC. Phone: (785) 625-4052

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
Well has casing leaks from 3250'-1500'.  
Arb-OH

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/12/2012 12:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

DS&W ran in hole to 2999'. Basic rigged to tubing, mixed and pumped 225 sx cement w/250 # hulls.  
Pulled tubing to 1000'. Basic rigged to tubing, mixed and pumped 75 sx cement to circulate cement to surface.  
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 35 sx cement w/50 # hulls. Maximum pressure 400 psi. Shut in pressure 300 psi.  
Rigged to 8 5/8" casing and pumped 15 sx cement w/200 psi. Cement circulated out of top of head on well. No shut in pressure.

Perfs:

Remarks: BASIC CEMENTING CO. TICKET # 6986

Plugged through: TBG

District: 04

Signed [Signature]  
10/08/12 (TECHNICIAN)

CM

SEP 12 2012

Form CP-2/3

RECEIVED  
SEP 17 2012  
KCC WICHITA