

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00112-00-02
Spot: SWSWNE Sec/Twnshp/Rge: 22-33S-43W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: HART A Well #: 1
County: MORTON Total Vertical Depth: 3425 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2570		WITH 2 SX CMT
CIBP		3146		
PROD	5.5	3416	0	WITH 600 SX CMT
SURF	8.625	332		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2012 8:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 08/24/2012 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

OXY CP-1 SHOWS TOC @ 2210' AFTER 2 SQUEEZE JOBS AT 3000' WITH 200 SX CMT & 2900' WITH 200 SX CMT. CASING PULLERS ONLY HAVE 2" OF STRETCH. RAN BOND LOG FROM 2300' TO 10' TO DETERMINE WHERE CMT IS BEHIND THE 5 1/2" CASING. BOND LOG INDICATES CMT THROUGH OUT THE ENTIRE LOGGED INTERVAL. CIBP @ 2570' WITH 2 SX CMT. RAN TBG TO 1400' & SPOTTED 25 SX CMT. PUMP 40 SX CMT FROM 350' TO 0'. PUMP 3 SX CMT DOWN ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3030	3050		
3016	3020		
2833	2839		
2800	2806		
2749	2756		
2710	2713		
2680	2688		
2630	2688		

RECEIVED
SEP 17 2012
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: TBG

District: 01

Signed Ken Jehlik
10/08/12 (TECHNICIAN)

RECEIVED
SEP - 5 2012
KCC DODGE CITY