

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-21205-00-00 *\* OR to inv. plug dt. 5 yr. cutoff.*  
Spot: S2NESESE Sec/Twnshp/Rge: 19-34S-2E  
890 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MCLAUGHLIN Well #: 2  
County: SUMNER Total Vertical Depth: 3249 feet

Operator License No.: 30253  
Op Name: CYCLONE PETROLEUM, INCORPORAT  
Address: 1030 W. MAIN  
JENKS, OK 74037

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3249		75 SX
SURF	8.625	240		145 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/22/2009 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: JAMES HAVER, DARREN B Company: CYCLONE PETROLEUM Phone: (918) 291-3200

Proposed Plugging Method: CIBP 3130' & 2 SKS. PERF AT 310 & CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE  
Date/Time Plugging Completed: 05/22/2009 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET 3130 & CAPPED WITH 2 SKS CMT. THE CASING WAS PERFORATED AT 300' & TUBING WAS RUN TO 315', WHERE CMT WAS CIRC'D TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3188	3207	CSG	

RECEIVED  
SEP 18 2012  
KCC WICHITA

Remarks: CONSOLIDATED CEMENT 60/40 4% GEL

Plugged through: TBG

District: 02

Signed

*[Signature]*  
11/08/12

(TECHNICIAN)

*JK*