

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20206
Spot: NWSENW Sec/Twnshp/Rge: 33-18S-15W
3300 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HARRIET BIRD Well #: 1
County: BARTON Total Vertical Depth: 3498 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1875		100 SX
SURF	8.625	879		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/18/2012 1:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated @ 880' and 250'.
Ran tubing to 1780'. Pumped 150 sx cement w/250 # hulls.
Pulled tubing to 800'. Pumped 125 sx cement and circulated cement to surface.
Pulled tubing. Tied to casing and pumped 20 sx cement pressured to 300 psi. Shut in.
Tied to surface. Pumped 30 sx cement pressured to 300 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
1780	1807		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE TICKET # 5689

Plugged through: TBG

District: 04

Signed Bruce Rodie
10/10/12 (TECHNICIAN)

CM

OCT 02 2012