

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21263-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 12-34S-28W
1305 feet from S Section Line, 3956 feet from E Section Line
Lease Name: HAGER Well #: 1-12
County: MEADE Total Vertical Depth: 6260 feet

Operator License No.: 34269
Op Name: APACHE CORPORATION
Address: 2000 POST OAK BLVD, STE 100
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		WITH 20 SX CMT
CIBP		5853		
PROD	5.5	6264	2020	WITH 240 SX CMT
SURF	8.625	1630		WITH 650 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2012 9:30 AM
Plug Co. License No.: 34703 Plug Co. Name: ROYALTY WELL SERVICE, INC.
Proposal Rcvd. from: MONTE KENT Company: APACHE CORPORATION Phone: (580) 273-8090

Proposed Plugging Method: CIBP @ 5600' WITH 20 SX CMT. PLUG AT 1700' WITH 65 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' TO SURFACE.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2012 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5000' WITH 20 SX CMT. 1ST PLUG AT 1710' WITH 65 SX CMT. LET SET 4 HOURS. TAGGED CMT AT 1600'. RAN TBG TO 1600' & PUMPED ANOTHER 65 SX CMT. 9/18/12: TAGGED TOC @ 1490'. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5843	5850		
5670	5680		

RECEIVED
OCT 09 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ROYALTY WELL SERVICE.

Plugged through: TBG

District: 01

Signed [Signature]
10/10/12 (TECHNICIAN)

RECEIVED
OCT - 9 2012
MD

KCC DODGE CITY