

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21253-00-00  
Spot: SENWSWSW Sec/Twnshp/Rge: 21-34S-27W  
683 feet from S Section Line, 4786 feet from E Section Line  
Lease Name: BARBY Well #: 2-21  
County: MEADE Total Vertical Depth: 5950 feet

Operator License No.: 34269  
Op Name: APACHE CORPORATION  
Address: 2000 POST OAK BLVD, STE 100  
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5500		WITH 20 SX CMT
COND	30	110		
PROD	4.5	5950	2045	WITH 430 SX CMT
SURF	8.625	1450		WITH 650 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/20/2012 11:00 AM

Plug Co. License No.: 34703 Plug Co. Name: ROYALTY WELL SERVICE, INC.

Proposal Revd. from: MONTE KENT Company: APACHE CORPORATION Phone: (580) 273-8090

Proposed Plugging Method: CIBP @ 5500' WITH 20 SX CMT. PLUG AT 1480' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/21/2012 12:30 PM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5500' WITH 20 SX CMT. SHOOT CASING OFF. CIRCULATE HOLE WITH MUD & 15 SX GEL. 1ST PLUG AT 1500' WITH 130 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5645	5654		
5607	5614		

RECEIVED  
OCT 09 2012  
KCC WICHITA

Remarks: USED COMMON CEMENT BY ROYALTY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Kenny Sullivan (TECHNICIAN)  
10/10/12

RECEIVED  
OCT - 8 2012  
KCC DULANE CITY

AMY