

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05263-00-00
Spot: N2SENE Sec/Twnshp/Rge: 14-12S-16W
3630 feet from S Section Line, 660 feet from E Section Line
Lease Name: SMITH Well #: A-3
County: ELLIS Total Vertical Depth: 3393 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3352		140 SX
SURF	8.625	692		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2012 9:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURTIS GABEL Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Ordered 510 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Perforations: 2786' - 2795', 3030' - 3036', 3083' - 3088', 3158' - 3162'.
PBTD - 3328'
Junk in hole
Dec. 1954; Casing leak @ 770'. Squeezed casing w/250 sx cement to surface on back side.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2012 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perforated @ 1650', 1018' and 600'.
Ran in hole with tubing to 2914'. Rigged to tubing and pumped 150 sx cement w/300 # hulls.
Pulled tubing to 1850' and pumped 80 sx cement w/200 # hulls.
Pulled tubing to 1050' and pumped 108 sx cement w/200 # hulls.
Circulated cement to pit area. Pulled tubing, rigged to 5 1/2" casing and topped with 30 sx cement. Hole standing full.
Rigged to 8 5/8" casing and there was instant pressure on backside.

Perfs:

Top	Bot	Thru	Comments
3158	3162		
3083	3088		
3030	3036		
2786	2795		


RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED EMENTING CO TICKET # 56541

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

SEP 26 2012