

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25957-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 3-15S-19W
4072 feet from S Section Line, 3436 feet from E Section Line
Lease Name: DOUG Well #: 1
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 32875
Op Name: BOWLES, C. W. DBA CWB - CO.
Address: PO BOX 186
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3700		
PROD	5.5	3797		150 SX
SURF	8.625	218		150 sx
T1	2.375	3695		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2012 10:30 AM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: JOEL STUHL Company: PRAIRIE HAWK WELL SERVICE L Phone: (785) 885-8240

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar @ 1328' w/175 sx cement.
CIBP @ 3700'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2012 1:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3508'. Rigged to tubing and pumped 18 sx gel followed by 50 sx cement w/200 # hulls.
Pulled tubing to 1850'. Rigged to tubing and pumped 100 sx w/300 # hulls.
Pulled tubing to 220'. Rigged to tubing and pumped 45 sx to circulate cement. Pulled tubing and topped off 5 1/2" casing with 5 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 4 sx w/100 psi. Shut in pressure 50 psi.

Perfs:

Top	Bot	Thru	Comments
3714	3718		
3540	3542		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING TICKET # 53565

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

SEP 28 2012