

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19032-00-00
Spot: NWNESW Sec/Twnshp/Rge: 10-19S-15W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SEEBER B Well #: 2
County: BARTON Total Vertical Depth: 3549 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3536		200 SX
SURF	10.75	899		350 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/17/2012 1:00 PM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 265-3311

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 11 sx gel

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/18/2012 3:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3300'. Pumped 11 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 1800'. Pumped 100 sx cement w/100 # hulls.
Pulled tubing to 900'. Circulated cement w/115 sx cement.
Pulled tubing. Tied to casing and pumped 70 sx cement. Circulated cement out surface pipe.
09/18/2012 - Topped off w/50 sx cement.

Perfs:

Top	Bot	Thru	Comments
3536	3549		
3469	3474		
3243	3301		
1781	1838		

RECEIVED
STATE CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE

Plugged through: ⁷⁶⁶CSG

District: 04

Signed Bruce Rodie
10/12/12 (TECHNICIAN)

CM