

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19291-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 16-11S-19W
3826 feet from S Section Line, 3002 feet from E Section Line
Lease Name: GILLBERG Well #: 2
County: ELLIS Total Vertical Depth: 3560 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3556 | | 150 SX |
| SURF | 8.625 | 171 | | 145 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2012 1:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Perforations: 3274 - 3490
DV Tool @ 1337' w/252 sx cement
Casing leaks

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2012 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3171'. Rigged to tubing and pumped 130 sx cement w/300 # hulls.
Pulled tubing to 1862'. Rigged to tubing and pumped 95 sx cement w/200 # hulls.
Pulled tubing to 916'. Rigged to tubing and pumped 110 sx cement w/200 # hulls to circulate cement to pit area.
Pulled tubing. Topped off 5 1/2" casing w/30 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

Perfs:


RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET # 56542

Plugged through: TBG

District: 04

Signed


10/12/12

(TECHNICIAN)

CM

SEP 27 2012