

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-3001-00-01
Spot: SEWNESW Sec/Twnshp/Rge: 28-28S-5W
2200 feet from S Section Line, 1825 feet from W Section Line
Lease Name: BOLINGER Well #: 1
County: KINGMAN Total Vertical Depth: 3905 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3905	2842	175 SX
SURF	8.625	247		200 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/13/2012 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: _____ Phone: (316) 524-1225

Proposed Plugging Method: According to the rules and regulations of the KCC.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/13/2012 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3780'-CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2842' PULLED CASING. RAN TUBING INTO 876' SPOTTED 50 SX CEMENT WITH 3/5 % CC, WAIT 2 HOURS. PULLED TUBING TO 356', LOADED HOLE 3 BARRELS. CIRCULATED TO SURFACE WITH 185 SX OF CEMENT FROM 356'.

Perfs:

Top	Bot	Thru	Comments
3856	3860		
3840	3846		

RECEIVED
OCT 10 2012
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40 4% POS MIX, TICKET #38079.

Plugged through: TBG

District: 02

Signed B. J. Hope
10/10/12 (TECHNICIAN)