

District Plugging Report

Operator License No: 101	String	Size	Depth	Pulled	Comments
Op Name: STATE OF KANSAS	DRIVE - Drive Pipe	8.000	20	0	EST.
Address 1: 130 S. MARKET	T1 - Tubing 1	6.250	552	0	EST.
Address 2:	T2 - Tubing 2	2.000	552	0	
City: WICHITA					
State: KS Zip Code: 67202 -					

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 6/24/11 / 1:30 pm
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report:

LOCATE AND DIG OUT WELL. FILL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 6/24/11 /4:30 pm KCC Agent: FRANK GUILFOYLE
Actual Plugging Report: Perfs: Top Bottom Thru

LOCATE AND DIG OUT WELL. DIG DOWN 4 FT TO STRAIGHT PIPE. CUT OF DP, 6.25" AND 2". SET SURFACE. RUN 1" AND REAMER TO 500 FT INSIDE OF 2". PILL PIPE. PERFORATE AT 300 FT AND 100 FT. RUN 1" TO 550 FT. WASH TO 552 FT. PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 98 SACKS OF CEMENT. EMPTY PIT AND BACKFILL. LEVEL AREA. WELL PLUGGED.

KANSAS CORPORATION COMMISSION

JUL 28 2011
RECEIVED

[illegible]

Remarks	CONTRACT NUMBER 11782. CATEGORY 2. CONTROL NO. 20110063-003. GPS'ed NAD 27. REG SEC
---------	---

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Frank S. [Signature]
(Technician)

Form: District Plugging Report –