

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23238-00-00
Spot: NENW Sec/Twnshp/Rge: 1-27S-23E
4638 feet from S Section Line, 3338 feet from E Section Line
Lease Name: RASTEGAR Well #: 3-1
County: BOURBON Total Vertical Depth: 498 feet

Operator License No.: 34420
Op Name: EXODUS GAS & OIL LLC
Address: 1701 WALNUT ST, 4TH FL
KANSAS CITY, MO 64108

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	484		88 SX CMT.
PROD	4.5	485		112 SX
SURF	8.625	201		88 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/25/2012 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STEVE LITTELL Company: _____ Phone: (620) 365-7555

Proposed Plugging Method: Set 50 foot cement plug from 484' to 434'. Set final cement plug from 100 feet to surface. Cut off casing 36" below ground level and weld on steel plate.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 05/29/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 4.5" casing to TD. Circulated cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. Cut the casing off below grade and filled in the pit.

Perfs:

RECEIVED

SEP 25 2012

KCC Chanute Dist. #3

RD

RECEIVED

SEP 28 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed _____
(TECHNICIAN)