

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22487-00-00
Spot: SENESE Sec/Twnshp/Rge: 17-18S-11W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: KRIER A Well #: 1
County: BARTON Total Vertical Depth: 3388 feet

Operator License No. ██████████

Op Name: KRIER ██████████ BA KRIER OIL OPERA

Address: PO BOX 763
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3382		100 SX
SURF	8.625	330		200SX

TION



Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/07/2012 9:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: ROGER KRIER

Company: KRIER OIL

Phone: (620) 793-5925

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/07/2012 2:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perforations. Topped w/5 sx cement.
Cut casing at 1485'. Pulled to 1450'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 900'. Pumped 75 sx cement w/100 # hulls.
Pulled casing to 630'. Pumped 50 sx cement w/50 # hulls.
Pulled casing to 250'. Circulated cement w/65 sx cement.
Pulled casing. Hole stayed full.

Top	Bot	Thru	Comments
3380	3392		
3254	3260		

RECEIVED
SEP 28 2012
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 734

Plugged through: CSG

District: 04

Signed

Bruce Rodie
10/10/12

(TECHNICIAN)

CM

SEP 19 2012

Form CP-2/3