

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-30350-00-00
Spot: SW Sec/Twnshp/Rge: 13-24S-17E
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DAVE KRAMER Well #: 1
County: ALLEN Total Vertical Depth: 1220 feet

Operator License No.: 32710
Op Name: LAYMON OIL II, LLC
Address: 1998 SQUIRREL RD
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1220		100 SX
SURF	8.625	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2012 12:00 AM
Plug Co. License No.: 32710 Plug Co. Name: LAYMON OIL II, LLC
Proposal Rcvd. from: MICHAEL LAYMON Company: _____ Phone: (620) 963-2495

Proposed Plugging Method: Run 2.3750 Tubing to 1220 feet then cement 10 sacks on bottom, 10 sacks at 450 feet, and 80 sacks from 300 feet to surface. Remove the 2.3750 tubing.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 03/09/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2.375" tubing to TD. Pumped 10 sacks of cement at TD. Pulled tubing to 450'. Pumped 10 sacks of cement at 450'. Pulled tubing to 300'. Circulated cement from 300' to surface. Pulled the rest of the tubing and topped the well off with cement. A total of 100 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

SEP 25 2012

KCC Chanute Dist. #3

KTD

RECEIVED

SEP 28 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
10/18/12 (TECHNICIAN)