

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-00187-00-00  
Spot: SENESENW Sec/Twnshp/Rge: 18-32S-1W  
3618 feet from S Section Line, 2961 feet from E Section Line  
Lease Name: O HARA Well #: 1  
County: SUMNER Total Vertical Depth: 3771 feet

Operator License No.: 7186

Op Name: DOCKING DEVELOPMENT COMPANY,

Address: PO BOX 928  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2725		
CIBP	5.5	2810		
PROD	5.5	3735		200 SX
SURF	8.625	354		350 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/10/2012 8:00 AM

Plug Co. License No.: 99981

Plug Co. Name: COPELAND ACID & CEMENT, INC.

Proposal Rcvd. from: LARRY BERTELSON

Company: DOCKING DEVELOPMENT

Phone: (620) 455-3444

Proposed  
Plugging  
Method: CIBP 2725' 2 SKS. PERF AT 500' & CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

Date/Time Plugging Completed: 09/10/2012 3:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 2725' & CAPPED WITH 2 SKS CMT. NO PIPE RECOVERED.  
CASING PERFORATED AT 500' & CEMENT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3256	3264	CSG	
2778	2779	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 01 2012  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID CEMENT. 60/40 4% GEL. 335 SX CEMENT. TA NOV LETTER

Plugged through: CSG

District: 02

Signed

  
10/15/12 (TECHNICIAN)