

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-203-20119-0000

LEASE NAME SHIMANEK

WELL NUMBER 1

4080 Ft. from S Section Line

2150 Ft. from E Section Line

SEC. 28 TWP. 19 RGE. 36 (E) or (W)

COUNTY Wichita

Date Well Completed 09/27/1995

Plugging Commenced 02/14/1996

Plugging Completed 02/15/1996

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR WOOLSEY PETROLEUM CORPORATION

ADDRESS 107 N MARKET STE 600 WICHITA KS 67202

PHONE# (316) 267-4379 OPERATORS LICENSE NO. 5506

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01/09/1996 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Winfield Depth to Top 2744 Bottom 2754 T.D. 3398

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surf	226	8-5/8"	226'	-0-
		surf	3398	4-1/2"	3398'	816'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Set CIBP @ 2660'. Pump 2 sx cement w/ bailer. Cut csg @ 816'. Pump 5 sx gel + 20 sx 60/40 pozmix + 2 sx gel cement from 776' to 700'. Mud from 200' to 280'. 40 sx 60/40 pozmix + 6% gel from 280' to 128'. Mud from 128' to 40'. 60/40 pozmix from 40' to 3'.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Post & Mastin License No. 08438

Address P.O. Box 297, Garden City, KS 67846


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Mark P. Stevenson, Vice-President-Operations (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) 107 N. Market, Wichita, KS 672



My appointment expires: March 4, 1998
 My Commission Expires: March 4, 1998
 Notary Public
Debra K. Clingan

RECEIVED
 STATE CORPORATION COMMISSION
 3-15-96
 MAR 15 1996
 CONFIRMATION DIVISION
 Wichita, Kansas