


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Finney County, Sec. 18 Twp. 23 Rge. 31W (E) (W)
Location as "NE/CNW/SW4" or footage from lines. C N2 N2
Lease Owner A. D. McKelvy
Lease Name Russell Well No. 1
Office Address c/o Graham Michaelis Drlg. Co. 211 N. Broadway, Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 10-10 19 58
Application for plugging filed November 24 19 59
Application for plugging approved November 24 19 59
Plugging commenced December 9 19 59
Plugging completed December 9 19 59
Reason for abandonment of well or producing formation Non commercial

If a producing well is abandoned, date of last production Was never produced 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot 405 E. 6th, St. John, Kansas
Producing formation Hugoton Depth to top 2665 Bottom 2719 Total Depth of Well 2790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herington	Gas	2665	2683	5"	2786	None
Krider	Gas	2683	2719			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

125 sacks cement by Cementing Co. 2500' to 2786'
16 sacks Gelled mud, Cementing Co. 2500' to top
Spotted 25 sacks cement at 450' thru 1 1/4" tubing with pump truck
Bridge at 35' Cemented to top.
Welded on metal cap.

STATE CORPORATION COMMISSION

DEC 29 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Yocum Well Service Co, Hooker, Oklahoma and Sun Cementing Co.
Address Liberal, Kansas

STATE OF Kansas, COUNTY OF Finney, ss.
Ralph Hinkle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Hinkle
Box 455, Garden City, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 59.

Gene C. Munn
Notary Public.

My commission expires June 13, 1962

15-055-00344
-0000

RUSSELL #1

WELL RECORD

LOCATION: C N/2 N/2 Sec. 18-T238-R31W Commenced: 8-6-58
 Finney County, Kansas Completed: 8-10-58
 (Rotary)

OPERATOR: Alfred D. McKelvy
 48 Lloyd Drive
 Atherton, California

CONTRACTOR: Graham-Michaelis Drilling Company
 211 North Broadway
 Wichita 2, Kansas

CASING RECORD: 5-1/2" 2786' w/300 sx poz w/1/4# Floceal; 300 sx
 poz and 200 sx comm

LOG

Sand	100'
Shale, Blue & Yellow	250'
Blue Shale & Gyp	400'
Shale & Red Bed	1200'
Red Bed, Gyp, Anhy & Sand	1261'
Red Bed & Gyp	1605'
Shale & Gyp	2110'
Shale, Gyp & Anhy	2225'
Dolomite & Shale	2476'
Shale & Anhy	2571'
Shale & Dolomite	2672'
Lime & Shale	2770' RTD

INDEXED
 RECORDED
 PETROLEUM DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MIC HAELIS DRILLING COMPANY

By John L. James
 Geologist

Subscribed and sworn to before me
 this 25th day of August, 1958

E. Gene Byrd
 E. Gene Byrd Notary Public
 My commission expires: 12/14/61