


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Finney County. Sec. 6 Twp. 21 Rge. 32 (E) (W) X  
Location as "NE/CNW&SW&S" or footage from lines SW/4  
Lease Owner A. D. McKelvy  
Lease Name Crozier Well No. \_\_\_\_\_  
Office Address 211 North Broadway - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 8-30-62 19\_\_\_\_  
Application for plugging approved 8-31-62 19\_\_\_\_  
Plugging commenced 9-14-62 19\_\_\_\_  
Plugging completed 9-18-62 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2707' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded off bottom - mixed and dumped 5 sacks cement  
Mudded hole to 300' - mixed and dumped 35 sacks cement  
Mudded to 45' mixed and dumped 15 sacks cement for top cap.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of Sept. 1962

My commission expires 24 October 1964  
Sidney D. Miller Notary Public.

AL MC KELVY

Appx. E/SW/4 6-21-32  
Finney County, Kansas

CROZIER #6

RTD 2708

Commenced 12/11/61

Completed 12/18/61

CONTRACTOR: Bennett &amp; Roberts Drilling, Inc.

Set 6 5/8" @ 324' w/175 sx cmt.

Set 5 1/2" @ 2707' w/300 sx cmt.

Sand & Shale	324'
Blue Shale	900
Sand	915
Shale	1100
Sand	1125
Shale	1300
Shale & Sand	1340
Red Bed	1525
Anhydrite	1550
Shale & Shells	1675
Sand	1800
Shale, Shells & Red Bed	1940
Shale, Lime & Red Bed	2285
Shale, Shells & Red Bed	2545
Lime, Shale & Red Bed	2695
Lime & Shale	2700

**RECEIVED**  
STATE OF KANSAS COMMISSIONER

OCT 8 1962

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS)

RUSSELL COUNTY ) SS.

I hereby certify that the above information is correct to the best  
of my knowledge.

BENNETT &amp; ROBERTS DRILLING, INC.

BY *Clare Hummel*

Subscribed and sworn to before me this 20th day of December, 1961.

*Clare Hummel*  
Notary Public

My Commission Expires 6/17/62