

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Perdue Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER 15-055-20,184 0000

LEASE NAME REED

WELL NUMBER #2

1375' Ft. from S Section Line

4015' Ft. from E Section Line

SEC. 9 TWP. 25 RGE. 31 ~~XXX~~ (W)

COUNTY FINNEY

Date Well Completed 3/11/75

Plugging Commenced 12/02/88

Plugging Completed 12/02/88

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 7 1988  
CONSERVATION DIVISION  
Wichita, Kansas  
LEASE OPERATOR MARDEN PRODUCTION COMPANY

ADDRESS P. O. Box 706

PHONE# (405) 340-6387 OPERATORS LICENSE NO. 9151

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/28/88 (date)

by Mr Paul Luthi and Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? none

Producing Formation Krider Depth to Top 2512' Bottom 2535' T.D. 2575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Krider	gas	2518	2525	4 1/2"	2570.5'	NONE
Surface	water	200'	0'	8 5/8"	330'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Loaded 4 1/2" casing to surface with fluid. Trip in 497' 2 3/8" tubing and spot 50 sacks cement through tubing to surface inside 4 1/2" casing. Tied onto 8 5/8" surface casing. Pumped down 150 sacks cement between surface and 4 1/2" casing to plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sam Mays Oilfield Services, Inc. License No. 8902

Address P. O. Box 62, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

David P. Williams (Employee of Operator) ~~XXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David P. Williams

(Address) P. O. Box 576; Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6<sup>th</sup> day of Dec., 1988.

Michael Johnson  
Notary Public

My Commission Expires: 3-10-92

