

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

YOUR COPY

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-203-20,100-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Falcon Exploration, Inc. KCC LICENSE # 5316
(owner/company name) (operator's)
ADDRESS 155 N. Market, Suite 1010 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE Oldham WELL# 1 SEC. 15 T. 18S R. 38 (East/West)

Approx SE - SE - SW SPOT LOCATION/QQQQ COUNTY Wichita

550' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

3190' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 349' CEMENTED WITH 60-40 posmix - 225 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3394'/3399' T.D. 5498' PBDT _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2550' w/50 sx; 2nd plug @ 1500' w/50 sx; 3rd plug @ 750' w/50 sx; 4th plug @ 380' w/50 sx; 5th plug at 40' w/10 sx' rathole 15 sx; Total 225 sx 60-40 posmix 6% gel 1/4# Floseal per sx.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE# (913) 674-5768

ADDRESS 216 E. McFarland City/State Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30884
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Began at 5:30 a.m. 5-8-93. 6-11-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: _____ AUTHORIZED OPERATOR/AGENT: Harold Maley
(signature)