

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19946-00-00

Spot: SESWSESE

Sec/Twnshp/Rge: 6-34S-12E

185 feet from S Section Line, 681 feet from E Section Line

Lease Name: BP

Well #: OW 1

County: CHAUTAUQUA

Total Vertical Depth: 1200 feet

Operator License No.: 32255

Op Name: KANSAS ENERGY COMPANY, L.L.C.

Address: BOX 68

SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	700	0	0 SX
SURF	10	20	0	0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/14/2012 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: P.J. BUCK

Company:

Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and plug with 20 sacks at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/16/2012 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Well had no production casing in it. Washed 1" to 700' gelled hole and spotted 25 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 120 sacks of cement were used to plug this well.

RECEIVED

OCT 11 2012

KCC Chanute Dist #3

DS

RECEIVED

OCT 18 2012


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


10/19/12 (TECHNICIAN)