

To: 1 020350
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-30 135
API NUMBER 13- 129-20,111 0000
C NW NW, SEC. 4, T 34 S, R 42 W 4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name McClain Well # 11-4

Operator: Coastal Oil & Gas

County Morton 154.60

Name & Address
1 Leadership Square, 211 N. Robinson
Suite 1700
Oklahoma City, OK 73102

Well Total Depth 4757 feet
Conductor Pipe: Size 13 3/8 feet 123
Surface Casing: Size 8 5/8 feet 1231

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Coastal Oil & Gas License Number 6593

Address 1 Leadership Sq., 211 N. Robinson, Ste. 1700, Oklahoma City, OK 73102

Company to plug at: Hour: 10 a.m. Day: 29 Month: 1 Year: 19 91

Plugging proposal received from Robert Martin

(company name) Coastal Oil & Gas (phone) 405-239-7031

were: 5 1/2" at 4430' w/250 sx cement to 3490', PBDT 4399', Perfs at 4313-19'
1st plug set CIBP at 4300' w/10 sx cement on top, mud 4290-1280',
2nd plug perforate 5 1/2" at 1230', pump and circulate 320 sx Class H cement,
filling 8 5/8" X 5 1/2" to surface. FEB 6 1991

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 30 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300' with 2 sx cement on top of plug with
bailer,
2nd plug tagged plug with tubing and circulated heavy mud, perforated at 1229-1230' with
4 shots. Pulled tubing to 1230' and circulated cement to surface. Cement top dropped
to 100', filled to surface with Redi-Mix on 1/30/91.

Remarks: Used 320 sx 60/40, 100 sx Class H, and heavy Redi-Mix by D & S. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (If ~~not~~ observed this plugging.)

DATE 2-11-91
INV. NO. 30646

Signed Glenn R. Barber (TECHNICIAN)