

1 120511

K-165-20781-0000

12-26

2888

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled '82 or '83  
NE NE, SEC. 11, T 16 S, R 18 WXX  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6216  
Operator: Edward P. Leiker  
Name & Address: HC 32 Box 132  
Hays, KS 67601

Lease Name Harvey Werth Well # 1  
County Rush 116.35  
Well Total Depth 3580 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1125

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 26 Month: 12 Year: 19 90

Plugging proposal received from Eddie Leiker  
(company name) Edward P. Leiker (phone) 913-625-5310

were: 4 1/2" at 3579', CIBP at 3517', Perfs at 3161-65'  
1st plug sand back to 3100' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 5 sx gel, 100 lbs. hulls, 50 sx cement, 15 sx gel, 100 lbs.  
hulls and 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 26 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3100' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped 300 lbs. hulls, 5 sx gel, 100 lbs. hulls, 50 sx cement, 15 sx gel, 100 lbs. hulls and 125 sx cement.  
Maximum pressure 600 psi and shut in 300 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1588' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-28-91

Signed Duane Rankin (TECHNICIAN)

INV. NO. 30555

12-26