

1030293

15.165.21845-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Not available
NW NE SE, SEC. 11, T 16 S, R 18 W/E
N SE Corner of
2310 feet from ~~N/S~~ section line
W SE Corner of
990 feet from ~~N/S~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6242

Lease Name Legleiter "A" Well # 1

Operator: Julius Legleiter

County Rush

Name & Address 505 East 20th

Well Total Depth 3780 ^{126.75} feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1145

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 4 Month: October Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3780' Perfs at 3004-3642'

1st plug pump 35 sx cement to bottom and stop plug at 2950'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 100 sx cement.

Plugging Proposal Received by Steve Duntz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 4 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3780' Perfs from 3004-3642'

1st plug pumped 35 sx cement to bottom and stopped plug at 2950', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 100 sx cement.

RECEIVED
OCT 09 1984

Remarks: Recovered 2900' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Steve Duntz
(TECHNICIAN)

DATE 10-15-84

INV. NO. 4288

15-165-21045-0000

STECKLEIN OIL COMPANY

PERFORATING RECORD

COMPANY
WELL
FIELD
County
State

COMPANY J. Legleiter
WELL A. Legleiter No. 1
FIELD _____
COUNTY Rush STATE Kansas

Location NW-NE-SE Other Services _____
Sec. 11 Twp 16S Rge 18W

Permanent Datum Ground Level Elev. 2006 Elev. KB 2011
Log Measured From Kelly Bushing 5 Ft. Above Perm. Datum DF _____
Casing Measured From Kelly Bushing GL 2006

CASING COLLARS AT			PERFORATED ZONES	
			Interval	No. of Holes
			from	
			to	
			from	
			to	
			from	
			to	
			from	
			to	

The above depths refer to:
 Log Measurement
 Drillers Measurement
 Others

CASING RECORD				Drillers T.D.
Size-in	Wt.-lbs.	Interval		3786
8 7/8		from 0 to 1145		
4 1/2		from 0 to 3780		log T.D. 3694
		from to		

Remarks _____

Run No. _____ Recorded By David F. Hertel & Don Stecker
Date 12-5-82 Witnessed By Mr. Legleiter