

1030295

165-21119-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Not Available  
NE, SEC. 7, T. 16 S, R. 18 W/E  
4950 feet from N SE Corner of XXX section line  
1220 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8879

Lease Name Legleiter Well # 1  
County Rush  
Well Total Depth 3655 118.79 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1205

Operator: C & W Oil  
Name & Address 1519 Hayney  
Hays, KS 67601

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 4 Month: October Year: 19 84

Plugging proposal received from Clay Duntz  
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3655' Perfs at 3214-3350

1st plug sand back to 3160' and dump 5 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Rement  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 4 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3655' Perfs from 3214-3350'

1st plug sanded back to 3160' and dumped 5 sx cement on top of sand through bailer,  
2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
released 8 5/8" rubber plug and pumped an additional 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 09 1984

Maximum pre-sure 650 psi and shut in pressure 500 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED  
(If you observe this plugging.)

DATE 10-15-84

Signed Steve Rement  
(TECHNICIAN)

INV. NO. 4281