

To: 1040999  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg.  
130 S. Market, Room 2078  
Wichita, KS 67202

9-15 API NUMBER 15-101-21,711-0000

PLUGGING SECTION W/2 SE SW, SEC. 33, T 16 S, R 30 WXE  
660 feet from S section line  
1650 feet from WXE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Wilkens Well # 1

Operator: John O. Farmer, Inc.

County Lane

Name: P.O. Box 352

Well Total Depth 4596 149.37 feet

Address: Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard JV, Inc. License Number 4958

Address: P.O. Box 1009, McPherson, KS 67460

Company to plug at: Hour: 11 a.m. Day: 15 Month: 9 Year: 1995

Plugging proposal received from Carol

(company name) Mallard JV, Inc. (phone) 316-241-4640

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2245-74'

1st plug at 2274' with 50 sx cement, 2nd plug at 1540' with 80 sx cement,

3rd plug at 700' with 50 sx cement, 4th plug at 280' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:30 p.m. Day: 15 Month: 9 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2274' with 50 sx cement,

2nd plug at 1540' with 80 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 280' with 40 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
CORPORATION COMMISSION  
SEP 18 1995  
9-18-95  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 65/35 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(CHECK) did not observe this plugging.

DATE 9-26-95

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 43583

9-15