

1 110152

7-21

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,522-0000

TECHNICIAN'S PLUGGING REPORT

App. C SW SE, SEC. 33, T 16 S, R 30 W/X

660 feet from S section line

1900 feet from E section line

Operator License # 3988

Lease Name Wilkens "GG" Well # 1

Operator: Slawson Exploration Company, Inc.

County Lane Lane 75.63

Name & Address 104 South Broadway

Well Total Depth 2327 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 4:30 a.m. Day: 21 Month: 7 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2866'  
Anhydrite 2262-83'

1st plug at 2285' with 40 sx cement, 2nd plug at 1250' with 80 sx cement,

3rd plug at 320' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James R. Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:15 a.m. Day: 21 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2285' with 40 sx cement,

2nd plug at 1250' with 80 sx cement,

3rd plug at 320' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7-31-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 8-1-89

INV. NO. 25486

Signed James R. Kapp  
(TECHNICIAN)