

To: 1 030641
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,271 - 0000
NE , SEC. 26, T 16 S, R 30 W/XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113
Operator: Landmark Oil Exploration and
Name & White & Ellis Drilling
Address 105 S. Broadway, Suite 1040
Wichita, KS 67202

2970 feet from S section line
1820 feet from E section line

Lease Name Sharp 'A' Well # 1-26
County Lane 149.83
Well Total Depth 4610 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 10 Month: January Year: 19 86

Plugging proposal received from Judy Steiben

(company name) White & Ellis - Great Bend (phone) 316-792-2424
Elevation 2848

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2242-2272'
1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement 3rd plug the surface pipe with
solid bridge 40 sx cement

4th plug hulls' - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:00 am Day: 11 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2245' with 50 sx cement, 2nd plug at 1370' with 80 sx
cement, 3rd plug at 340' with 40 sx cement, 4th & 5th plug - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15
sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1986
1-16-86
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-16-86

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 12090