

1080322

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-20,916-0000
NE NE SE SEC. 26, T 16 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DIREEN WELL # 1-A

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 149.50

OPERATOR LICENSE # 6009

WELL TOTAL DEPTH 4600 FEET

OPERATOR: DOUBLE EAGLE EXPLORATION PRODUCTION CSG: SIZE 4 1/2" @ 4599' WITH 175 SX

NAME AND 221 S BROADWAY, SUITE 310 SURFACE CASING: SIZE 8 5/8" @ 350' WITH 20 SX

ADDRESS WICHITA, KS 67202

RECEIVED
STATE CORPORATION COMMISSION
8-1-00
AUG 1 2000

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A 8-1-00

OTHER WELL AS HEREINAFTER INDICATED _____ CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 25 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4559-63 & 4526-35

CASING LEAK BRIDGED OFF @ 2600' SPOT 4 SX CEMENT WITH BAILER. SHOOT CASING AT 1250'. RUN TUBING IN HOLE TO 1250'. PUMP 10 SX GEL, 80 SX CEMENT, 200# HULLS & 25 SX CEMENT. PULLED TUBING TO 625' WAITED ON MORE HULLS, PUMPED 400# HULLS & 50 SX CEMENT. CIRCULATED TO SURFACE PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 20 SX CEMENT. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 3 SX CEMENT. PRESSURED TO 500#. SHUT IN. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:15 PM DAY: 25 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT CASING LEAK BRIDGED OFF AT 2600' SPOT 4 SX CEMENT WITH BAILER. SHOT CASING @ 1250'. RUN TUBING IN HOLE TO 1250'. PUMP 10 SX GEL, 80 SX CEMENT, 200# HULLS & 25 SX CEMENT. PULLED TUBING TO 625'. WAITED ON MORE HULLS. PUMPED 400# HULLS & 50 SX CEMENT. CIRCULATED TO SURFACE. PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 20 SX CEMENT. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 3SX CEMENT. PRESSURED UP TO 500#. SHUT IN.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED
DATE 8/3/00
SIGNED Kevin D. Strube
(TECHNICIAN)
FORM CP-2/3
WV. NO. 1060308