

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20902-00-00
Spot: CSWSWSW Sec/Twnshp/Rge: 26-16S-30W
330 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: DIRREEN Well Number: 1
County: LANE Total Vertical Depth: 4612 feet

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W. 47TH STREET, STE 318
KANSAS CITY, MO 64112

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 345
Production: Size 4.5 feet: 4348 WITH 200 SX CMT
Liner: Size _____ feet: 18149.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/05/2001 10:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: PUMP 40 SX CMT & 200# HULLS. PUMP GEL TO 2000'. CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/05/2001 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 3940-4245'. DV TOOL AT 2005' CEMENTED WITH 300 SX CMT. CIRCULATED TO SURFACE. 1ST PLUG PUMP 40 SX CMT & 200# HULLS. DISPLACE WITH 12 SX GEL TO 2005'. FILL CASING TO SURFACE WITH 120 SX CMT. MAXIMUM PRESSURE 2500#. SHUT IN WITH 1500#. TIE ONTO BACKSIDE AND PUMPED 10 SX CMT. PRESSURED TO 500# AND HELD.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 12 2001
7-12-01
CONSERVATION DIVISION

INVOICED
DATE 7-12-01
WELL NO. 2002060058

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

JUL 09 2001

Form CP-2/3

MP