

1060188

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,809-0000

SW NW NW, SEC. 26, T 16 S, R 30 W/EX

990 feet from N/NE section line

330 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Lease Name Sharp Well # 1

Operator: Midco Exploration, Inc.

County Lane

Name & Address 411 Farmers & Bankers Building

Well Total Depth 4625 150.31 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:10 pm Day: 28 Month: February Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2 set at 4625

1st plug sand back to 4480' and dump 4 sx cement on top of sand

2nd plug pumped through head with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped additional 120 sx cement

Maximum pressure 900# and shut-in pressure 300#

Plugging Proposal Received by Paul A. Luthie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 pm Day: 28 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4625

1st plug sand back to 4480' and dump 4 sx cement on top of sand. 2nd plug pumped through head with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls and released

8 5/8" rubber plug and pumped additional 120 sx cement.

Maximum pressure 900# and shut-in pressure 300#

Remarks: Use 60/40 Pozmix 2% gel 3%CC by Allied. They recovered 1200' of 4 1/2 casing.  
(if additional description is necessary, use BACK of this form.)

I (did) not observe this plug

DATE 2/7/84

INV. NO. 0562

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
MAR 07 1984  
3-7-84

Paul A. Luthie  
(TECHNICIAN)