

1 060012

1-26

299R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,535-0000

SW NE SE, SEC. 25, T 16 S, R 30 W/E

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Dickey Well # 1-25

Operator: Landmark Oil Exploration, Inc.
Name & Address: 250 North Water, Suite 308
Wichita, KS 67202

County Lane 149.24
Well Total Depth 4592 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Company License Number 5883

Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 4 p.m. Day: 26 Month: 1 Year: 19 90

Plugging proposal received from Marrison Burris

(company name) Warrior Drilling Company (phone) 316-262-3791
Elevation 2836'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2248-79'

1st plug at 2290' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,

3rd plug at 420' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 6:30 p.m. Day: 26 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2290' with 50 sx cement,

2nd plug at 1400' with 80 sx cement,

3rd plug at 420' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
FEB 07 1990

(If you did not observe this plugging.

DATE _____

Signed _____ (TECHNICIAN)

INV. NO. 27348

1-26