

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-21996-00-00  
Spot: NE Sec/Twnshp/Rge: 19-24S-17E  
1320 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: WILLIE Well #: 1  
County: WOODSON Total Vertical Depth: 1260 feet

Operator License No.: 34047  
Op Name: RON-BOB OIL LLC  
Address: 1607 MAIN ST.  
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1217		130 SX
SURF	7	41		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2012 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: ROBERT CHRIESTENSON Company: \_\_\_\_\_ Phone: (620) 365-0919

Proposed  
Plugging  
Method:

Run 1" into 4.5" to bottom and run 1" behind 4.5" to bottom, then cement from bottom to surface.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 05/23/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 4.5" casing to TD. Ran 1/2" pipe down the backside of the 4.5" casing inside the 7" surface casing to 260' where cement was encountered. Circulated cement through the 1" pipe inside the 4.5" from TD to surface. Pulled 600' of 1" pipe. Circulated cement through the 1/2" pipe from 260' to surface. Pulled 1/2" pipe out of the hole. Pumped cement through the 1" pipe from 600' to surface. Pulled the rest of the 1" pipe out of the hole and topped the well off with cement. A total of 187 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
SEP 26 2012  
KCC Chanute Dist. #3

RD

RECEIVED  
SEP 28 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

*[Signature]*  
\_\_\_\_\_  
(TECHNICIAN)