

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23366-00-00
Spot: SWSESWNW Sec/Twnshp/Rge: 32-22S-13W
2531 feet from N Section Line, 788 feet from W Section Line
Lease Name: GRIMES/CORNWELL Well #: 1-32
County: STAFFORD Total Vertical Depth: 3890 feet

Operator License No.: 3959
Op Name: SIROKY OIL MANAGEMENT
Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3650		
CIBP		3791		
PROD	4.5	3933	1982	WITH 125 SX CMT
SURF	8.625	265		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2012 8:00 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: SPENCER SIROKY Company: SIROKY OIL MANAGEMENT Phone: (620) 672-5625

Proposed Plugging Method: SAND BACK TO 3560' & PUT 4 SX CMT ON TOP OF BRIDGE. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2012 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3560' & PUT 7 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3837	3854		VIOLA
3677	3684		LANSING
3616	3620		LANSING

RECEIVED
OCT 09 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

OCT - 2 2012

KCC DODGE CITY

Signed

(TECHNICIAN)

AWY