

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20143-00-00
Spot: SWSE Sec/Twnshp/Rge: 16-3S-41W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ROBERT WALTER A Well #: 4
County: CHEYENNE Total Vertical Depth: 1474 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2101 CEDAR SPRINGS RD, STE 1500
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1470		70 SX
SURF	7	93		65 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/18/2012 9:00 AM
Plug Co. License No.: 33532 Plug Co. Name: ADVANCED DRILLING TECHNOLOGIES LLC
Proposal Rcvd. from: TOM ROELFS Company: ROSEWOOD RES. INC. Phone: (970) 324-1686

Proposed Plugging Method: 7" surface casing set @ 93' w/65 sx cement.
4 1/2" production casing set @ 1470' w/ 70 sx cement.
TD 1474'. PBTD 1439'. Perforations: 1342'-1358'.
Ordered 150 sx common cement w/100 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2012 11:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 4 1/2" production casing. Pumped 112 sx common cement w/100 # hulls.
Maximum pressure 300 psi.
Connected to 7" surface casing. Pumped 9 sx common cement. Maximum pressure 400 psi.

Perfs:

Top	Bot	Thru	Comments
1342	1358		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: ADT CEMENT

Plugged through: CSG

District: 04

Signed Darrel Dipman
10/19/12 (TECHNICIAN)

CM

SEP 19 2012