

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21322-00-00
Spot: S2SESE Sec/Twnshp/Rge: 24-28S-16W
337 feet from S Section Line, 663 feet from E Section Line
Lease Name: THORPE Well #: 3
County: KIOWA Total Vertical Depth: 4749 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4624		WITH 3 SX CMT
PROD	4.5	4796	0	WITH 140 SX CMT
SURF	8.625	321		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2012 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2012 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

4 1/2" CIBP IS SET AT 4624' WITH 3 SX CMT. PACKER CEMENTED AT 3100' WITH 84 JOINTS OF 2 3/8" TBG CEMENTED IN HOLE. CASING LEAK SQUEEZED AT 3340' WITH 190 SX CMT. PERFORATE @ 464'. PUMP DOWN 4 1/2" CASING WITH 200 SX CMT, FILLING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS TO SURFACE WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4677	4707		

RECEIVED
OCT 09 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Stephen J. Puffer
(TECHNICIAN)

RECEIVED
OCT - 2 2012
KCC DODGE CITY

AKL