

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101- 20,932- 0000

NW NW SW, Sec. 25, T 16 S, R 30 WXX

2310 feet from ~~XX~~/S section line

330 feet from W/~~XX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5405

Lease Name Dickey Well # 3

Operator: Oil Capital Corporation
Name & 411 Farmers & Bankers Bldg.
Address Wichita, KS 67202

County Lane

Well Total Depth 4600 feet 149.50

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 26 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Harold Maley

(company name) Abercrombie (phone) 316-793-8186

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2260' with 50 sx cement

2nd plug at 1020' with 60 sx cement

3rd plug at 390' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement

Signed Steve [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 am Day: 26 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement, 2nd plug at 1020' with

60 sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole

with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing

RECEIVED
STATE CORPORATION COMMISSION
2-29-84
FEB 29 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~/ did not) observe this plugging.

Signed Steve [Signature]
(TECHNICIAN) ✓

INVOICED

DATE 3-8-84

INV. NO. 0604